## 23 7313: EXISTING AIR HANDLING UNIT SCHEDULE

		SUPPLY FAN			RETURN FAN		MAX AIRFLOW CONDITION		MAX ECON AIRFLOW		MIN AIRFLOW	W HEATING WATER COIL			COOLING COIL						FILTERS	WEIGH				
		MAX FAN	SA ESP,	FANS	MAX FAN	EA ESP,	FANS	SA	OA	EA	OA	EA	SA		EAT	LAT	WPD,	TTL	SENS	EAT	LVG COIL	LVG UNIT	. \	WPD,	MA, IN	
MARK		CFM	IN WC	HP	CFM	IN WC	HP	CFM	CFM	CFM	CFM	CFM	CFM	MBH GP	M DB, °I	F DB, °F	FT	МВН	МВН	DB/WB, °F	DB/WB °F	DB/WB °F	GPM	FT	(MERV-8)	LBS.
AHU-2E	EXISTING CONDITIONS	10600	1.90	10	9300	0.50	2	10600	1300	9300	10600	9300	8200	156 6.	0 56	73	0.1	408	314	80/66	53/53	53/53	58.0	4	2	3710
AHU-2E	NEW CONDITIONS	9355	1.90	10	8055	0.50	2	8120	1945	8055	9355	8055	2710		-	-	-	-	-	-	-	-	-	-	-	-
AHU-2W	EXISTING CONDITIONS	10400	2.00	10	9900	0.50	2	10400	1850	9900	10400	9900	8170	178 7.	5 52	72	0.2	447	330	82/67	51/51	53/52	63.6	12	2	3670
AHU-2W	NEW CONDITIONS	9655	2.00	10	9155	0.50	2	8350	2430	9155	9655	9155	3040	-   -	-	-	-	-	-	-	-	-	-	-	-	-

NOTES: APPLY TO ALL MARKS, UNO.

- EXISTING PERFORMANCE BASED ON RECORD DRAWINGS.
- 2. VERIFY EXISTING AHU PERFORMANCE PRIOR TO DEMOLITION OF SECOND FLOOR.

AHU-2E		VENTILATION TABLE									
				VUSBC 2	012 CFM	DESIG	N CFM		ZONE	CFM	
	ROOM	SQFT	occ	OA	EA	EA	MAX SA	HVAC ZONE	MIN	MAX	
241	OFFICE	115	2	25	-		280	TU-M203	180	84	
243	OFFICE	115	2	25	-		280				
245	OFFICE	115	2	25	-		280				
247	OFFICE	170	2	30	-		405	ATU-OD-247	120	40	
249	OFFICE	115	2	25	-		275	ATU-OC-249	70	27	
251	TEAM ROOM	125	6	50	-		270	ATU-OC-251	70	27	
253	OFFICE	105	2	25	-		285	ATU-OE-255	180	85	
257	OFFICE	105	2	25	-		285				
255	OFFICE	105	2	25	-		285				
259	OFFICE	105	2	25	-		285	TU-M218	180	85	
263	OFFICE	105	2	25	-		285				
261	OFFICE	105	2	25	-		285				
240, C244, 244	OPEN OFFICE	955	15	170	-		450	ATU-OD-240	210	450	
260	LIBRARY	105	2	30	-		100	ATU-OA-260	60	100	
213	OPEN OFFICE	470	20	165	-		780	ATU-OF-213	210	780	
217	MEETING ROOM	210	10	80	-		250	ATU-OC-217	100	250	
225	MEETING ROOM	200	10	80	-		250	ATU-OC-225	100	250	
218	WORK/COPY	180	2	30	-		75	ATU-OB-218	70	18	
218	CORRIDORS	175	-	15	-		60				
C230	STAIR	95	-	10	-		35				
220	JANITOR CLOSET	70	-	-	70	70	15				
C210	LOBBY	295	-	25	-		110	ATU-OC-C210	70	25	
T212	MEN	230	-	-	420	420	45				
T218	WOMEN	170	-	-	140	140	30				
C216	STAIRS	160	-	15	-		30				
C214	ELEV	70	-	-	-		25				
T210	RESTROOM	60	-	-	70	70	15				
256	ROBOT	105	2	45	-		225	ATU-OB-256	60	22	
229	OPEN OFFICE	520	17	150	-		760	TU-M206	190	76	
231	OPEN OFFICE	630	13	130	-		1,010	ATU-OF-231	250	1,27	
231	РВ	86	-	15	-		230				
231	STORAGE	85	-	15	-		30				
223, 225, c227	OPEN OFFICE/CORRIDOR	1,285	28	275	-		740	TU-M208	340	81	
C211	CORRIDOR	135	-	15	-		70				
254, C250, 258	OPEN OFFICE	1,140	18	200	-		520	TU-M216	250	52	
OOMS: 35		8,816	165	1,795	700	700	9,355	ZONES: 18	2,710	9,35	

NOTES:

- OUTSIDE AIR VALUES LISTED ARE UNCORRECTED FOR ZONE AIR DISTRIBUTION EFFECTIVENESS (Ez). APPLY EFFECTIVENESS VALUE
  OF 0.8 (CEILING SUPPLY OF WARM AIR WITH CEILING RETURN, PER ASHRAE 62.1-2007 TABLE 6-2) WHEN ZONE IS IN HEATING MODE.
   ALL ROOMS WITH EXHAUST AIR SERVED VIA EXHAUST FANS, UNO.
- 3. EXISTING TU MINIMUM AIRFLOWS LISTED ARE BASED ON DESIGN HEATING/VENTILATION REQUIREMENTS. BAS AND TAB CONTRACTOR TO VERIFY EXISTING/REPLACED TU AIRFLOW MONITORING RING IS CAPABLE OF PROVIDING ACCURATE AIRFLOW AT SCHEDULED MINIMUM SUBMIT TAB DATA FOR ALL ATU AND TU AT MINIMM AND MAXIMUM AIRFLOWS.

AHU-2W	ATION TABL										
	ROOM			VUSBC 2			N CFM		ZONE CFM		
	SQFT	occ	OA EA		EA	MAX SA	HVAC ZONE	MIN	MAX		
269	OFFICE	105	2	25	-		285	TU-M229	180	85	
267	OFFICE	105	2	25	-		285				
265	OFFICE	105	2	25	-		285				
273	OFFICE	105	2	25	-		285	TU-M232	120	57	
271	OFFICE	105	2	25	-		285				
275	OFFICE	120	2	25	-		285	ATU-OD-275	120	57	
277	OFFICE	105	2	25	-		285				
279	OFFICE	165	2	25	-		430	ATU-OD-279	120	43	
281	OFFICE	155	2	25	-		330	ATU-OD-281	120	66	
283	OFFICE	155	2	25	-		330				
285	OPEN OFFICE	265	2	35	-		365	ATU-OD-285	70	36	
274	OFFICE	95	2	20	-		55	ATU-OA-274	50	11	
286	OFFICE	95	2	20	-		55				
204	TEAM ROOM	160	6	50	-		125	ATU-OA-204	60	12	
208	KITCHENETTE	175	5	90	-		250	TU-M230	120	26	
206	CLOSET	30	-	5	-		10				
203	PERIMETER	525	10	105	-		755	ATU-OF-203	180	75	
272, 270, C260	OPEN OFFICE	960	13	155	-		465	TU-M231	190	46	
C200	CORRIDOR	85	-	10	-		155	ATU-OC-C200	120	24	
C201	LOBBY	245	-	20	-		85				
203	ARENA	1,310	12	175	-		570	TU-M223	220	57	
203	GATHERING	740	18	170	-		475	TU-M220	220	47	
276, C280, C270	OPEN OFFICE	665	11	120	-		345	ATU-OC-276	150	34	
211	CONFERENCE	425	20	160	-		430	TU-M219	200	43	
201	MAKER	1,645	31	635	-	2,430	2,430	ATU-OF-201	500	1,50	
								TU-M225	300	93	
OOMS: 25		8,645	152	2,020	_	2,430	9,655	ZONES: 17	3,040	9,65	

NOTE:

- OUTSIDE AIR VALUES LISTED ARE UNCORRECTED FOR ZONE AIR DISTRIBUTION EFFECTIVENESS (Ez). APPLY EFFECTIVENESS VALUE
  OF 0.8 (CEILING SUPPLY OF WARM AIR WITH CEILING RETURN, PER ASHRAE 62.1-2007 TABLE 6-2) WHEN ZONE IS IN HEATING MODE.
   ALL ROOMS WITH EXHAUST AIR SERVED VIA EXHAUST FANS, UNO.
- 3. EXISTING TU MINIMUM AIRFLOWS LISTED ARE BASED ON DESIGN HEATING/VENTILATION REQUIREMENTS. BAS AND TAB CONTRACTOR TO VERIFY EXISTING/REPLACED TU AIRFLOW MONITORING RING IS CAPABLE OF PROVIDING ACCURATE AIRFLOW AT SCHEDULED MINIMUM SUBMIT TAB DATA FOR ALL ATU AND TU AT MINIMM AND MAXIMUM AIRFLOWS.

design group

Facilities Planning & Construction 575 Alderman Rd / PO Box 400726 Charlottesville, VA 22904 /434-982-4621

2rv CONSULTANTS IN

100 10th Street NE, Ste. 202 Charlottesville, VA 22902 T) 434.296.2116

SECOND FLOOR RENOVATIONS OLSSON HALL; BUILDING NO. 0202

> record Drawings

VENTILATION TABLES

DATE: 04/23/18
DRAWN BY: CJP/BNM
CHECKED BY: PMM
REVISIONS

PROJECT NUMBER P04406

M0.3